KOLAR DIVISION.

ADVERTISEMENT. 453

The 2nd February 1893.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 15th February 1893, for constructing a new School building at Kolar. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1894.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A. M. and 4 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a new School building at Kolar"; in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor, will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Description of Work.	Per.	Rate.	Quantity
Earthwork (excavation and filling)	C. Yds.		626
Stone in chunam (foundation and basement)	C. Ft.		13,028
Brick in chunam (superstructure)	"		11,591
Semicircular arch work	"		751
Plastering with chunam	Sq.		185
Pointing basement	"		$11\frac{1}{2}$
White washing, inside	"		$98\frac{1}{2}$
Color washing, outside	"		$86\frac{1}{2}$
Flooring with concrete and plastering	"		$28\frac{1}{2}$
Do do foundation	C. Ft.		5,751
Stone flagging for Verandah	Sq.		$16\frac{1}{2}$
Matting with outer rinds of bamboos	"		$29\frac{1}{2}$
Cornice, $1\frac{1}{2}$ feet deep	R. Ft.		995
String course	"		378
Stone slabs (dressed)	Sq. Ft.		955
Do do	"		5,862
Mangalore Tile roofing	Sq.		26·00
Ridging with chunam	R. Ft.		122
Pakka terrace	Sq.		$18\frac{1}{2}$
Bangal do	"		$19\frac{1}{2}$
Teak wood work	C. Ft.		841
Eave boards	R. Ft.		408
Iron work of truss	No.		6
Doors $4' \times 7'$ with fan light	"		26
Do $4' \times 7'$	"		4
Windows $3' \times 4\frac{1}{2}'$ with fan light	"		12
Ventilators $4' \times 2'$	"		18
Wood oiling and painting doors	L. S.		..
Guttering for the terrace roof and drainage for leaves of main roof to prevent damage to Bengal roof	"		
Sun shades for the side room doors	No.		4
Wooden screens, movable	Sq. Ft.		493
Including gate, &c., Railway charges and fitting complete ..	L. S.		..
Clearing site and road making	"		..
Fittings to the laboratory such as head gutters	"		..
Latrine as per plan	..		..

Y. SRINIVASA RAO,
Executive Engineer.

HASSAN DIVISION.

ADVERTISEMENT.

The 2nd February 1893.

Tenders are hereby invited for constructing an Anikat across and excavating channel from the Shankutirtha stream in Hassan Taluk.

2. The plans, estimates, schedule of rates and conditions may be seen at the Executive Engineer's Office between the hours of 11 A. M. and 4 P. M. daily.

3. Printed forms of tender will be supplied on application, free of cost, by the Executive Engineer. These forms should be filled in, signed by the contractor and forwarded in sealed covers to the Executive Engineer before the 28th February 1893. The work should be completed by the end of 30th June 1896.

4. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

5. No tenders will be received unless accompanied by a deposit of Rs. 500 as earnest money.

6. Within 8 days of the acceptance of the tender, the contractor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be taken to meet any loss that may be sustained by Government.

7. The name of the contractor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries respecting the acceptance or rejection of a tender will receive any reply whatever.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned to applicants in due course.

9. An approximate estimate of quantities of items of work required is given below. These quantities are not guaranteed :—

Description of Work.	Quantity.	Per.
Excavation	L. S.	..
Blasting rock and cutting foundation	100	C. Yds.
Burnt and rubble stone in surki mortar	13,352	C. Ft.
Painting with cement	44·61	Sqr.
Lifting gear and shutters	L. S.	..
Burnt stone slabs	2,382	Sq. Ft.
Cut stone slabs	702	Do
Burnt stone in surki	5,453	C. Ft.
Cut stone work	367	Do
Cut stone groves	39	Rg. Ft.
Rough stone work, new	840	C. Yds.
Training bank, clearing rear anikat and baling water	L. S.	..
Pointing with mortar	5·92	Sq.
Earth filling	50	C. Yds.
Gravelling roadway	8	Do
Screw gearing, teak shutters, &c., for sluice	175	No.
Excavating channel and deep cutting	43,728	C. Yd.
Removing bolders and silt dams	L. S.	..
Do jungle	5	Miles.
Mile stones including zero stones	8	No.
Bank grade stones	49	Do
Channel grade stones	57	Do
Brick in surki	8,175	C. Ft.
Plastering with mortar	23·12	Sq.
Rough stone apron	351	C. Yds.
Plastering with surki	2·57	Sq.
Pointing with do	26·98	Do
Guard stones	28	No.
Mangalore pipes	288	Do
Clay concrete	1,368	C. Ft.
Plugs with rods	20	No.
Gravelling roadway and making approaches	L. S.	..

B. ANANTA RAMAIYA,
for *Executive Engineer.*